

Nr	Podstawa	Opis robót	Jm	Ilość
Podbicia				
1	KNNR 2 1108/02	Boazerie z listew drewnianych 17,20*2*1,0+(5,68+0,6)*4,08*2	m2	85,64
		razem	m2	85,64
2	KNNR 2 1108/05	Dwukrotne malowanie Fobosem (analogia) 17,20*2*1,0+(5,68+0,6)*4,08*2	m2	85,64
		razem	m2	85,64
Okladziony scian i kominów płytkami kamiennymi				
3	KNNR 2 1002/01	Licowanie płytkami kamiennymi o wymiarach 25x6cm 1,05*0,46*4 1,05*0,36*8 1,05*0,64*4 6*1,35*1,3	m2 m2 m2 m2	1,93 3,02 2,69 10,53
		razem	m2	18,17
Ruszt i elewacja z desek				
4	KNNR 2 1108/01	Ruszt drewniany na ścianach (3,69+19,2)*2*3,28 0,2*(1,0*3*7+1,0*8+2,25*12+2,35*4+1,9) -(1,0*1,0*7+1,0*2,25*6+1,0*2,35*2+1,9*2,35)	m2 m2 m2	150,16 13,46 -29,67
		razem	m2	133,95
5	KNNR 2 1108/02	Boazerie z listew drewnianych (3,69+19,2)*2*3,28 0,2*(1,0*3*7+1,0*8+2,25*12+2,35*4+1,9) -(1,0*1,0*7+1,0*2,25*6+1,0*2,35*2+1,9*2,35)	m2 m2 m2	150,16 13,46 -29,67
		razem	m2	133,95
6	KNNR 2 1108/05	Dwukrotne lakierowanie boazerii (3,69+19,2)*2*3,28 0,2*(1,0*3*7+1,0*8+2,25*12+2,35*4+1,9) -(1,0*1,0*7+1,0*2,25*6+1,0*2,35*2+1,9*2,35)	m2 m2 m2	150,16 13,46 -29,67
		razem	m2	133,95